

Sl. No.	Items of work	Unit	Rates estimated	Quantity	Rates to be quoted
4	Burnt brick in lime "mortar"	C.ft.	Rs. a. p. 0 4 0	5,472	Rs.
5	Burnt stone slabs 5 to 6" thick one line dressed for exposed faces and fixed in lime mortar (old burnt stone slabs available at site)	S.ft.	0 2 0	928	
6	Providing trusses and fixing including painting, etc., as per Marin's specifications 10' from centre to centre	Cwt.	16 0 0	66	
7	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	389	
8	Roofing with 1st Class Mangalore pattern tiles on teak wood reapers 2" x 1"	Sqr.	22 0 0	59.84	
9	Teakwood doors frames 4" x 5" with panelled shutters 1½" thick folding doors with hinges, bolts, painting, etc., complete	S.ft.	1 12 0	68	
9a	Providing and fixing teak wood doors frames 3½" x 4" panelled shutters 1½" thick with hinges, bolts painting, etc., complete	"	1 8 0	77	
10	Teakwood windows with frames 3" x 4" with iron bars ¾" dia. 4½" c to c with glazed shutters hinges, etc., complete, expanded metal fixed inside, painting, etc., complete	"	2 0 0	288	
11	Chunam plastering	Sqr.	3 0 0	80.05	
11a	White washing 2 coats	"	0 4 0	80.05	
12	Flooring with burnt stone slabs over 3" lime mortar quoin dressing and fixed	Sqr.	20 0 0	39.00	
13	Mortar band over roofing	R.ft.	0 3 0	84	
14	Teakwood eave board from 12" to 9" wide ¾" thick including painting	"	0 8 0	360	
15	Mangalore ridge tiles set in mortar	"	0 7 0	136	
16	Cement pointing to basement	Sqr.	3 0 0	6.64	
17	Drilling holes in slabs for fixing girders	Each	0 4 0	54	
18	Providing and fixing R.C. ventilators	Sq.ft.	1 0 0	12	
19	Fixing R. S. Tatas tested girders above big doors including hoisting fixing and painting 6" x 3" at 12 lbs.	Cwt.	14 0 0	2.14	
20	Boxing girders with terrace brick in cement mortar	R.ft.	0 6 0	10	
21	Constructing steps in front of doors with available slabs	L.S.	..	..	20
22	Dismantling old mantapam design building now used as lumber Stores Shed as per details below: (a) Removing parapet wall 1½ x 1½ of burnt brick in mortar including coping (b) Removing burnt stone slab roofing with cement and stacking at places (c) Removing beams 1' x 1' x 6' (d) Removing vertical pillars (11½' high) and stacking (e) Removing capitals (f) Removing size stone in mortar and removing debris (g) Removing burnt stone slab flooring	R.ft. Sqr. Each " " C.ft. Sqr.	0 0 4 3 0 0 0 8 0 0 8 0 0 4 0 0 0 4 3 0 0	290 26.04 60 40 40 5,195 2,301	
23	Old size stone in lime mortar	C.ft.	0 2 6	2,924	

B. R. GARUDACHAR,  
*Executive Engineer.*

#### MANDYA DIVISION.

*Abstract Notification dated 16th December 1938.*

The attention of the public is hereby invited to the Advertisement, published in pages 2267-2271 of the issue, dated 22nd December 1938 in *Mysore Gazette*, calling for tenders for constructing District Hospital at Mandya.

The last date of receipt of tender is up to 12 noon on 9th January 1939.

M. V. KRISHNASWAMY IYENGAR,  
*Executive Engineer.*